



Gamsby and Mannerow
ENGINEERS



ADDENDUM No. 1

TOWN OF SOUTH BRUCE PENINSULA WIARTON INFLUENT WORKS UPGRADE

Our File: 211068

August 22, 2011

Contractors are advised of the following questions that arose following the Site Meeting on August 18th, 2011:

1. The Purchasing Procedures for Bidders Clause 27.4 indicates that the 100% Performance Bond is to remain valid for 12 months, but the Town of South Bruce Peninsula Performance Bond template indicates that the Bond is to be valid for 2 years?
The bond template may be edited to require a one-year (12 month) Performance Bond period to match the Town's purchasing procedures.
2. Additional Information for Bidders Clause 3.7 (page 13) indicates Tender for Items 1 to 11 are to be included – should it say 11 or 12?
Correct, this should say Items 1 to 12.
3. Division 1 Section 1T013301T – Submittals – Clause 1.9.3 requires a WSIB Clearance and Statutory Declaration for each payment?
A WSIB Clearance and Statutory Declaration will be required prior to the issuance of the Substantial Performance Payment Certificate and also prior to the issuance of the Release of Holdback Payment Certificate.
4. Division 2 Section 2T025322T – Sanitary Forcemains 2.2.3 & 2.3.7 indicates anodes and tape wrap are required on metallic fittings. Does this apply to both buried fittings and those inside the valve chamber?
Anodes and tape wrap are only required on buried fittings, not those within the valve chamber. Those within valve chamber will be either stainless steel or protected against corrosion with epoxy pipe coating.
5. Division 2 - 2.2.8 requires one 8 guage copper tracer wire but 3.7.1 requires 2 - #12 steel core tracer wires?
Tracer wire should be 8 guage TWU multistrand copper (single).
6. Division 2 – you are requiring CCTV inspections of the forcemain 3.1, and hydrostatic testing 3.11. Does this apply only to the new by-pass forcemains or all new piping prior to connection to existing?
The two new by-pass forcemains and valve chamber piping should all be pressure tested prior to connection to existing. It will not be possible to pressure test the influent pipe. CCTV inspection is required only for the new influent pipe, which cannot be pressure tested.


people engineering environments

Gamsby and Mannerow Limited • Guelph, Owen Sound, Listowel, Kitchener, Exeter

1260 - 2nd Avenue E, Unit 1 Owen Sound, ON N4K 2J3 519-376-1805 fax 519-376-8977 www.gamsby.com

The tenderer shall sign and submit a copy of this Addendum attached to the Form of Tender.

Issued by,
GAMSBY AND MANNEROW LIMITED,
Per:



J. B. Slocombe, P.Eng.

JBS/kd

Contractor:

cc: Christine Beard-Laaber (tsbppwmassist@bmts.com)
Paul McLennan (pmclennan@gamsby.com)
Amanda Pepping (apepping@gamsby.com)
Allen-Hastings Limited (hastings1234@sympatico.ca)
Bud Mervyn Construction (bmcl@bmcl.ca)
Harold Sutherland Construction (andrew@hsc-ltd.com)
Xterra Construction Inc. (xterra@bellnet.ca)
SMRS Construction (smrsconstruction@bellnet.ca)
Bridge Construction (pbridge@amtelecom.net)
File No. 211068

