

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 13
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part A - General Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| A 1 | Mobilization & Demobilization | 1.00 | LS | | |
| A 2 | Field Office | 1.00 | LS | | |
| A 3 | Bonding and Insurance | 1.00 | LS | | |
| A 4 | Traffic Control Signing | 1.00 | LS | | |
| A 5 | Pedestrian Staging | | | | |
| | a) Pedestrian Bridge | 1.00 | LS | | |
| | b) Pedestrian Access Corridors | 1.00 | LS | | |
| A 6 | Precondition Survey | 1.00 | LS | | |
| A 7 | As-Built Drawings | 1.00 | LS | | |
| A 8 | Ground Mounted Project Identification Signs | 1.00 | LS | | |
| A 9 | CCTV Inspection - Sanitary Sewers (Preconstruction Inspection & Service Locates) | 1,100.00 | m | | |
| A 10 | CCTV Inspection - Storm Sewers (Preconstruction Inspection & Service Locates) | 1,100.00 | m | | |
| A 11 | Vac Truck Conflict Investigation | 100.00 | hr | | |
| A 12 | Dewatering - Well Points | | | | |
| | a) Berford Street | 700.00 | m | | |
| | b) Division Street and Oil/ Grit Separator | 1.00 | LS | | |
| A 13 | Electronic Message Boards (x4) | 13.00 | mth | | |
| A 14 | Pay Duty | 50.00 | hrs | | |
| A 15 | Construction Layout | 1.00 | LS | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 14
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part B - Removals Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|------|------------------|----------------|
| B 1 | Preparing Right of Way | 1.00 | LS | | |
| B 2 | Clearing | 10.00 | ea | | |
| B 3 | Grubbing | 10.00 | ea | | |
| B 4 | Removal of Existing Asphalt - Roadway - Asphalt | 11,750.00 | m2 | | |
| B 5 | Removal of Driveways (All Types), Boulevards and Sundry Concrete Pavements | 6,000.00 | m2 | | |
| B 6 | Cutting Existing Pavement (Road Only) | 150.00 | m | | |
| B 7 | Removal of Concrete Curb and Gutter | 2,750.00 | m | | |
| B 8 | Removal of Existing Concrete Sidewalk | 4,600.00 | m2 | | |
| B 9 | Removal of Maintenance Holes, Catchbasins, Ditch Inlets and Valve Chambers | | | | |
| | a) Storm Structures | 52.00 | ea | | |
| | b) Sanitary Structures | 14.00 | ea | | |
| | c) Valve Chamber | 1.00 | ea | | |
| B10 | Removal of Sewers & Watermain Pipe | | | | |
| | a) Storm | 1,400.00 | m | | |
| | b) Sanitary | 1,200.00 | m | | |
| | c) Watermain | 1,500.00 | m | | |
| B 11 | Abandon Sewers and Watermain Pipe (Provisional) | | | | |
| | a) Cap & Seal | 10.00 | ea | | |
| | b) Grout Pipe | 25.00 | m3 | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 15

ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part B - Removals Pg. 2

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|------|------------------|----------------|
| B 12 | Removal and Salvage of Fire Hydrants | 8.00 | ea | | |
| B 13 | Removal of Existing Signs | 74.00 | ea | | |
| B 14 | Removal and Re-Installation of Existing Signs (Reinforced Concrete Base) | 11.00 | ea | | |
| B 15 | Remove and Salvage Ped Signal Assembly including Poles, Lights, Arm and Signals at George Street | 1.00 | LS | | |
| B 16 | Removal of Coal Shoots | 5.00 | ea | | |
| B 17 | Removal and Salvage of Benches & Garbage Bins | 20.00 | ea | | |
| B 18 | Removal and Salvage of Existing Street Lights | | | | |
| | a) Decorative Street Light | 29.00 | ea | | |
| | b) Cobra Head and Arm on Utility Pole | 14.00 | ea | | |
| | c) Cobra Head, Arm and Concrete Pole | 1.00 | ea | | |
| B 19 | Remove, Salvage and Re-Install Interlock Paving Stones | 100.00 | m2 | | |
| B 20 | Removal and Replacement of Doorway Steps and Ramps (Provisional) | | | | |
| | a) New Concrete Ramps | 50.00 | m2 | | |
| | b) New Concrete Step | 15.00 | m2 | | |
| B 21 | Removal and Disposal Asbestos Pipe (Transite) Material (Provisional) | 50.00 | t | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 16
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part C - Road Surface Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| C 1 | a) Earth Excavation (Grading) P.Q. | 14,000.00 | m3 | | |
| | b) Management of Subject Waste Local (Provisional) | 700.00 | m3 | | |
| | c) Management of Subject Waste Non Local (Provisional) | 300.00 | m3 | | |
| | d) Sub Excavation of Unsuitable Soil | 500.00 | m3 | | |
| C 2 | Granular A | 8,800.00 | t | | |
| C 3 | Granular B, Type II | 22,000.00 | t | | |
| C 4 | Hot Mix HL-3 HMA Surface Course (2021) | | | | |
| | a) HL 3 HMA or EQ.Superpave | 1,600.00 | t | | |
| | b) HL 3 FC HMA or EQ.Superpave | 800.00 | t | | |
| C 5 | Hot Mix HL-3 HMA Coloured Surface Course Provisional (2021) or EQ.Superpave | 200.00 | t | | |
| C 6 | Hot Mix HL-3 HMA Surface Course (2020) - Parking Areas or EQ.Superpave | 250.00 | t | | |
| C 7 | Hot Mix HL-8 HMA Binder Course (2020) - Parking Areas or EQ.Superpave | 250.00 | t | | |
| C 8 | Hot Mix HL-8 HMA Binder Course (2020) or EQ.Superpave | 3,800.00 | t | | |
| C 9 | Temporary Asphalt | | | | |
| | a) Cold Patch | 60.00 | t | | |
| | b) HL 3 HMA or EQ.Superpave | 250.00 | t | | |
| C 10 | Asphalt Curb Ramping | 2,800.00 | m | | |
| C 11 | Tack Coat | 15,000.00 | m2 | | |
| C 12 | Asphalt Driveways | 1,000.00 | m2 | | |
| C 13 | Asphalt Boulevard | 600.00 | m2 | | |
| C 14 | Concrete Curb & Gutter, All Types | | | | |
| | a) 600.040 | 2,100.00 | m | | |
| | b) 600.100 - Mountable | 900.00 | m | | |
| | c) 600.080 Barrier Curb w/Narrow Gutter Super Elevated Modified | 1,000.00 | m | | |
| | d) OPSD 600.110 Modified Barrier Curb (Planting Bed) | 1,000.00 | m | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 17

ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part C - Road Surface Pg. 2

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| C 15 | Supply and Install 1.5 M Concrete Sidewalk as per OPSD-310.010 Modified With Saw Cut Panels | 3,600.00 | m2 | | |
| C 16 | Tactile Walking Surface Indicators (Set) | 25.00 | ea | | |
| C 17 | Coloured Concrete - Boulevards & Islands | 1,800.00 | m2 | | |
| C 18 | Coloured Concrete Adjustment Strip | 750.00 | m2 | | |
| C 19 | Pipe Subdrain in Filter Sock (OPSD 216.021 & 809.010) | 3,300.00 | m | | |
| C 20 | Adjust Existing Utility Structures | 7.00 | ea | | |
| C 21 | Adjust Existing Catch Basin and Maintenance Holes (All Types) | 10.00 | ea | | |
| C 22 | Water for Dust Suppression | 1,000.00 | m3 | | |
| C 23 | Calcium Chloride Solid | 500.00 | kg | | |
| C 24 | Pavement Marking (Road - 2 Coats) | 2,000.00 | m | | |
| C 25 | Pavement Marking (Parking Bays) | 500.00 | m | | |
| C 26 | Pavement Marking, Durable | | PQ | | |
| | a) Pavement Marking Durable, Line Work | 1,500.00 | m | | |
| | b) Pavement Marking Durable, Stop Bars | 470.00 | m | | |
| | c) Pavement Marking Durable, Crosswalk Lines | 240.00 | m | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 18
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part C - Road Surface Pg. 3

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|----------------|------------------|----------------|
| C 27 | Pavement Marking Symbols, Durable a) Directional Arrows | 25.00 | ea | | |
| C 28 | Pavement Marking, Temporary | 2,500.00 | m | | |
| C 29 | Pavement Marking Symbols, Temporary | 30.00 | ea | | |
| C 30 | Pavement Marking Removals a) Obliteration | 1,000.00 | m | | |
| | b) Soda Blasting | 250.00 | m | | |
| C 31 | Pavement Marking Symbol Removals a) Obliteration | 5.00 | ea | | |
| | b) Soda Blasting | 5.00 | ea | | |
| C 32 | New Traffic Signs | 112.00 | ea | | |
| C 33 | Adjust Watermain Valve Boxes | 10.00 | ea | | |
| C 34 | Adjust Curb Stop Valve Boxes | 10.00 | ea | | |
| C 35 | Topsoil, Imported | 2,750.00 | m ² | | |
| C 36 | Sodding | 2,750.00 | m ² | | |
| C37 | Temporary Driveway Access a) Foodland | 1.00 | LS | | |
| | b) Petro | 1.00 | LS | | |
| C 38 | Steel Bollards | 2.00 | ea | | |
| C 39 | Hydro Pole Support (Provisional) | 10.00 | each | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 19
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part D - Sanitary Sewers Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|------|------------------|----------------|
| D 1 | 1200 dia. PC Sanitary MH (OPSD - 701.010) | 24.00 | ea | | |
| D 2 | 200 mm dia. PVC (DR35) Sanitary Sewer | 35.00 | m | | |
| D 3 | 250 mm dia. PVC (DR35) Sanitary Sewer | 975.00 | m | | |
| D 4 | 300 mm dia. PVC (DR35) Sanitary Sewer | 330.00 | m | | |
| D 5 | 375 mm dia. PVC (DR35) Sanitary Sewer | 21.00 | m | | |
| D 6 | 125 mm dia. (SDR28 - green) Sanitary Services - Residential | 104.00 | ea | | |
| D 7 | 150 mm dia. (SDR28 - green) Sanitary Services - Commercial (Provisional) | 10.00 | ea | | |
| D 8 | Break into Ex. Sanitary Structure, Connect & Make Good (Provisional) | 4.00 | ea | | |
| D 9 | Connect to Existing Sanitary Sewer | 16.00 | ea | | |
| D 10 | CCTV Inspection, Mandrel Testing & Flushing - Sanitary Sewers | | | | |
| | a) Substantial Completion | 1,361.00 | m | | |
| | b) Warranty Period | 1,361.00 | m | | |
| D 11 | Self-Leveling Maintenance Hole Frame and Grates | 24.00 | ea | | |
| D 12 | Temporary Staging Connection | 4.00 | ea | | |
| D 13 | Granular B Type II (Provisional) | 200.00 | t | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 20
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part E - Storm Sewers Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|------------|---|-------------------|------|------------------|----------------|
| E 1 | 1200 dia. PC MH | 16.00 | ea | | |
| E 2 | 1500 dia. PC MH | 5.00 | ea | | |
| E 3 | 2400 dia. PC MH | 8.00 | ea | | |
| E 4 | 3000 dia. PC MH | 1.00 | ea | | |
| E 5 | 600 x 600 CB | 18.00 | ea | | |
| E 6 | 600 x 1200 DCB | 31.00 | ea | | |
| E 7 | 250 dia. Storm Sewer | 82.00 | m | | |
| E 8 | 300 dia. Storm Sewer | 175.00 | m | | |
| E 9 | 375 dia. Storm Sewer | 305.00 | m | | |
| E 10 | 450 dia. Storm Sewer | 153.00 | m | | |
| E 11 | 525 dia. Conc Storm Sewer | 6.50 | m | | |
| E 12 | 600 dia. Conc Storm Sewer | 145.00 | m | | |
| E 13 | 675 dia. Conc Storm Sewer (Provisional) | 18.50 | m | | |
| E 14 | 750 dia. Conc Storm Sewer | 114.00 | m | | |
| E 15 | 1200 dia. Conc Storm Sewer (50 D) | 455.00 | m | | |
| E 16 | 1200 dia. Conc Storm Sewer (65 D) | 200.00 | m | | |
| E 17 | Oil-Grit Separator Model CDS PMSU40_30 | 1.00 | ea | | |
| E 18 | Division Street Storm By-Pass Stage 1A | 1.00 | LS | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 21
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part E - Storm Sewers Pg. 2

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| E 19 | Connect to Existing Storm Sewer | 5.00 | ea | | |
| E 20 | CCTV Inspection, Mandrel Testing (375 mm and Under) & Flushing - Storm Sewers | | | | |
| | a) Substantial Completion | 740.00 | m | | |
| | b) Warranty Period | 740.00 | m | | |
| E 21 | Self-Leveling Maintenance Hole Frame and Grates | 28.00 | ea | | |
| E 22 | Temporary Staging Connections | 4.00 | ea | | |
| E 23 | Granular B Type 2 (Provisional) | 100.00 | t | | |
| E 24 | Storm Service (125 mm Ø) | | | | |
| | a) Storm Service Long > 10 m | 20.00 | ea | | |
| | b) Storm Service Short < or = to 10 m | 20.00 | ea | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 22

ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part F - Watermain Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|--------------|--|-------------------|-----------|------------------|----------------|
| F 1 | 100 dia. Watermain, Incl. Fittings, Tees, Bends, Corrosion Protection (zinc nuts) and Restraints | 25.00 | m | | |
| F2 | 150 dia. Watermain, Incl. Fittings, Tees, Bends, Corrosion Protection (zinc nuts) and Restraints | 250.00 | m | | |
| F 3 | 200 dia. Watermain, Incl. Fittings, Tees, Bends, Corrosion Protection (zinc nuts) and Restraints | 250.00 | m | | |
| F 4 | 300 dia. Watermain, Incl. Fittings, Tees, Bends, Corrosion Protection (zinc nuts) and Restraints | 1,185.00 | m | | |
| F 5 | 350 dia. Watermain, Incl. Fittings, Tees, Bends, Corrosion Protection (zinc nuts) and Restraints | 20.00 | m | | |
| F 6 | 100 mm Dia. Gate Valve | 2.00 | ea | | |
| F 7 | 150 mm Dia. Gate Valve | 5.00 | ea | | |
| F 7-1 | 200 mm Dia. Gate Valve | 4.00 | ea | | |
| F 8 | 300 mm Dia. Gate Valve | 12.00 | ea | | |
| F 8-1 | 350 mm Dia. Gate Valve | 1.00 | ea | | |
| F 9 | 25 mm PE 200 Water Service C/W all Appurtenances (Commercial) | 71.00 | ea | | |
| F10 | 50 mm PE 200 Water Service C/W all Appurtenances (Provisional) | 5.00 | ea | | |
| F11 | Supply and Install Hydrant Sets, including Valves and Leads | 11.00 | ea | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 23
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part F - Watermain Pg. 2

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| F 12 | 50 mm PE 200 Flushing Hydrant | 2.00 | ea | | |
| F 13 | Connect to Existing Watermain | 7.00 | ea | | |
| F 14 | Temporary Staging Connection(s) | 5.00 | ea | | |
| F 15 | Commissioning & Testing of Watermain | 1.00 | LS | | |
| F 16 | Temporary Water Supply System | 1.00 | LS | | |
| F 17 | Water Service 50 mm Conduit with Insulation | 40.00 | ea | | |
| F 18 | Insulation of Watermain (Provisional) | 50.00 | m | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 24
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part G - Street Lights Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|------|------------------|----------------|
| G 1 | Power Supply Cables + GND 3/C #3 AWG + GND Cu, RWU90 | 100.00 | m | | |
| G 2 | Street Lighting Cables + GND 3/C #6 AWG + GND Cu, RWU90 | 1,200.00 | m | | |
| G 3 | Luminaire Riser Cables + GND 2/C #12 AWG + GND Cu, RW90 | 340.00 | m | | |
| G 4 | Power Supply (Load Centre c/w Panelboard) | 2.00 | ea | | |
| G 5 | Installation of Concrete Footing for Base Mounted Pole | 16.00 | ea | | |
| G 6 | Supply and Installation of Aluminum Pole c/w Duplex Receptacle and Banner Savers | 22.00 | ea | | |
| G 7 | 100W LED decorative Luminaires c/w Long Life Photocell | 37.00 | ea | | |
| G 8 | Installation of 6' Decorative Bracket | 37.00 | ea | | |
| G 9 | 40W LED decorative Luminaires c/w Long Life Photocell | 37.00 | ea | | |
| G 10 | Installation of Aluminum Bracket | 37.00 | ea | | |
| G 11 | Rigid PVC, Direct Buried | 100.00 | m | | |
| G 12 | Rigid PVC, Concrete Encased (2 Ducts) | 250.00 | m | | |
| G 13 | Ground Electrodes (3000 mm x 19 mm) | 14.00 | ea | | |
| G 14 | Trench Excavations | 100.00 | m | | |
| G 15 | Energizing Street Lighting System | | | | |
| | a) ESA Inspection Fees | 1.00 | LS | | |
| | b) Testing and Acceptance of Work | 1.00 | LS | | |
| G 16 | Utility Duct Bank (As per Detail) | | | | |
| | a) Boulevard | 1,200.00 | m | | |
| | b) Road Crossings | 120.00 | m | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 25
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part H - Traffic Signals Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| H 1 | Electrical Handholes, 460 mm dia. (OPSD 2112.020) | | | | |
| | a) William Street | 3.00 | ea | | |
| | b) George Street | 3.00 | ea | | |
| | c) Frank Street | 3.00 | ea | | |
| H 2 | Electrical Handholes, 675 mm dia. (OPSD 2112.030) | | | | |
| | a) William Street | 1.00 | ea | | |
| | b) George Street | 1.00 | ea | | |
| | c) Frank Street | 1.00 | ea | | |
| H 3 | Rigid Ducts, Direct Buried, 75 mm dia. | | | | |
| | a) William Street | 206.50 | m | | |
| | b) George Street | 197.50 | m | | |
| | c) Frank Street | 227.20 | m | | |
| H 4 | Rigid Ducts, Direct Buried, 2 x 50 mm dia. | | | | |
| | a) William Street | 27.50 | m | | |
| | b) George Street | 32.20 | m | | |
| | c) Frank Street | 48.30 | m | | |
| H 5 | Rigid Ducts, Direct Buried, 1 x 50 mm + 1 x 75 mm dia. | | | | |
| | a) William Street | 16.40 | m | | |
| | b) George Street | 35.40 | m | | |
| | c) Frank Street | 38.20 | m | | |
| H 6 | Rigid Ducts, Direct Buried, 4 x 100 mm dia. | | | | |
| | a) William Street | 715.80 | m | | |
| | b) George Street | 699.10 | m | | |
| | c) Frank Street | 797.50 | m | | |
| | | | | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 26
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part H - Traffic Signals Pg. 2

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|--|-------------------|------|------------------|----------------|
| H 7 | Cable Systems | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 8 | Power Supply | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 9 | Traffic Signal Steel Poles (Black), Base Mounted | | | | |
| | a) William Street | 8.00 | ea | | |
| | b) George Street | 8.00 | ea | | |
| | c) Frank Street | 8.00 | ea | | |
| H 10 | Concrete Footings in Earth | | | | |
| | a) William Street | 8.00 | ea | | |
| | b) George Street | 8.00 | ea | | |
| | c) Frank Street | 8.00 | ea | | |
| H 11 | Decorative Intersection Lighting Luminaires, Mast Arms & Brackets (Black) | | | | |
| | a) William Street | 4.00 | ea | | |
| | b) George Street | 4.00 | ea | | |
| | c) Frank Street | 4.00 | ea | | |
| H 12 | Single Member Arms and Signal Hangers (Black) | | | | |
| | a) William Street | 8.00 | ea | | |
| | b) George Street | 8.00 | ea | | |
| | c) Frank Street | 8.00 | ea | | |
| H 13 | Special Type Signal Heads | | | | |
| | a) Frank Street | 1.00 | ea | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1

Page No. 27

ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part H - Traffic Signals Pg. 3

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| H 14 | Highway Type Signal Heads | | | | |
| | a) William Street | 8.00 | ea | | |
| | b) George Street | 8.00 | ea | | |
| | c) Frank Street | 7.00 | ea | | |
| H 15 | Pedestrian Type Signal Heads | | | | |
| | a) William Street | 8.00 | ea | | |
| | b) George Street | 8.00 | ea | | |
| | c) Frank Street | 8.00 | ea | | |
| H 16 | Accessible Pedestrian Push Button Systems | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 17 | Audible Pedestrian Signal | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 18 | Traffic Signal Pre-Emption Equipment | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 19 | Traffic Signal Controller and Cabinet | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 20 | Microwave Detection System | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 28
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part H - Traffic Signals Pg. 4

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|-------------------------------------|-------------------|------|------------------|----------------|
| H 21 | Temporary Traffic Signals | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 22 | Removal of Existing Traffic Signals | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| H 23 | Video Detection (Provisional) | | | | |
| | a) William Street | 1.00 | LS | | |
| | b) George Street | 1.00 | LS | | |
| | c) Frank Street | 1.00 | LS | | |
| | | | | SUBTOTAL: | |

SCHEDULE OF UNIT PRICES

R. J. Burnside & Associates Limited

Project No. 300050111.1
Page No. 29
ADDENDUM NO. 3

Contractor: ***

Address: ***

Contract Title: Berford Street Reconstruction and Streetscaping Improvement

Part I - Landscaping Pg. 1

| ITEM NO. | DESCRIPTION | CONTRACT QUANTITY | UNIT | UNIT PRICE | CONTRACT TOTAL |
|----------|---|-------------------|------|------------------|----------------|
| 11 | Metal Bicycle Rack | 16.00 | ea | | |
| 12 | Garbage Cans | 20.00 | ea | | |
| 13 | Sail Shade Structure - Allowance Design / Build | 2.00 | ea | \$20,000.00 | \$40,000.00 |
| 14 | Stone and Timber Benchs - Allowance Design / Build | 14.00 | ea | \$2,000.00 | \$28,000.00 |
| 15 | Custom Fabricated Guardrail | 50.00 | m | | |
| 16 | Limestone Slab Feature | 6.00 | ea | | |
| 17 | Street Trees | 65.00 | ea | | |
| 18 | Shrub & Perennial | 1,300.00 | ea | | |
| 19 | Mulch | 180.00 | m3 | | |
| 110 | Planting Soil Mixture | 1,000.00 | m3 | | |
| | | | | SUBTOTAL: | |